Concrete Estimate

Slab volumes worked out in cubic yards

YOUR LOGO

SolidBase Concrete Contractors

123 Business Road · Your City, ST 00000 · (555) 010-2030 · hello@yourcompany.com

Work: Driveway replacement + walkway

Mix: 4,000 PSI, fibre-reinforced

Finish: Broom finish, sealed

Customer Greg Hollis

Site 301 Meadow Drive, Fort Worth

Quote No. CON-2026-0208

Date 11/18/2026

STEP 1 · SLAB DIMENSIONS

Slab / pour	Length (ft)	Width (ft)	Depth (in)	Volume (cu yd)
Driveway	40.0	18.0	5.0	**11.11**
Apron at street	18.0	6.0	6.0	**2.00**
Front walkway	30.0	4.0	4.0	**1.48**
Porch landing	8.0	6.0	4.0	**0.59**
			Total volume	**15.19**

STEP 2 · SETTINGS

Over-order allowance % (5-10)	8
Concrete to order (cu yd)	**16.50**
Total finished area (sq ft) from the take-off	**996**
Forms / edges (lin ft)	196

STEP 3 · PRICE (quantities come from the take-off)

Item	Qty	Unit	Rate	Amount
Ready-mix concrete 4,000 PSI	**16.5**	cu yd	$165.00	**$2,722.50**
Demo & haul away old concrete	**996.0**	sq ft	$2.25	**$2,241.00**
Gravel base 4" compacted	**996.0**	sq ft	$1.10	**$1,095.60**
Rebar #3 @ 18" grid	**996.0**	sq ft	$0.95	**$946.20**
Forming & finishing labour	**996.0**	sq ft	$3.60	**$3,585.60**
Saw-cut control joints & sealer	**996.0**	sq ft	$0.55	**$547.80**

Terms

- Price assumes truck access within 60 ft of the pour; pump charged extra if needed.
- Concrete cracks are controlled with saw cuts; hairline shrinkage cracks are normal and not a defect.
- Keep vehicles off new driveways for 7 days; full strength at 28 days.
- 1/3 deposit to schedule, balance on the day of the pour.

Subtotal	$11,138.70
Tax %	0.00
Tax	$0.00
TOTAL	**$11,138.70**
Deposit %	33
Deposit due	$3,675.77

Accepted by: _____ Date: _____

Cream cells = measurements, yellow = settings. Add rows inside each table; all quantities and totals recalculate.