GRANITE STATE FLATWORK

123 Business Road · Your City, ST 00000 · (555) 010-2030 · hello@yourcompany.com
Driveways, patios & flatwork

YOUR LOGO

No. CON-2026-0221
11/18/2026

DRIVEWAY ESTIMATE

CLIENT	SITE	PROJECT	SIZE
Angela Moreno	19 Sunset Terrace, Albuquerque	New 2-car driveway	24 ft x 36 ft = 864 sq ft

THICKNESS	BASE
5" with thickened edges	6" compacted aggregate

WORK ITEM	QTY	UNIT	RATE	AMOUNT
Excavate & grade to 11" depth	864	sq ft	$1.60	**$1,382.40**
Aggregate base 6" compacted	864	sq ft	$1.35	**$1,166.40**
Rebar #4 @ 24" on chairs	864	sq ft	$1.10	**$950.40**
Concrete 4,500 PSI air-entrained	14.5	cu yd	$170.00	**$2,465.00**
Place, finish & broom texture	864	sq ft	$3.25	**$2,808.00**
Control joints & cure/seal	864	sq ft	$0.60	**$518.40**

Subtotal	$9,290.60
Tax (0%)	$0.00
TOTAL ▶	**$9,290.60**

CONCRETE MIX & SITE SPECIFICATION

Strength	4,500 PSI	**Slump**	4" ± 1"	**Air**	5-7% entrained	**Fibre**	Polypropylene
Reinforcing	#4 rebar 24" o.c.	**Joints**	Every 10-12 ft	**Cure**	Spray-on cure & seal	**Drive on**	After 7 days

TERMS & CONDITIONS

- Price assumes truck access within 60 ft of the pour; pump charged extra if needed.
- Concrete cracks are controlled with saw cuts; hairline shrinkage cracks are normal and not a defect.
- Keep vehicles off new driveways for 7 days; full strength at 28 days.
- 1/3 deposit to schedule, balance on the day of the pour.

Client approval

Date