YOUR LOGO

BrightSpark Electrical Contractors
Licensed electrical contractors

Electrical Quote

No. ELC-2026-0141 · 11/12/2026

CUSTOMER
Olivia Bennett
77 Cedar Lane, Charlotte

JOB DETAILS
Job type: Kitchen rewire + panel upgrade
Panel: 100A to 200A upgrade

SCHEDULE
Estimated time: 2 days, 1 electrician + 1 helper
Inspection: City permit & final inspection included

CIRCUIT SCHEDULE

CIRCUIT	BREAKER	WIRE	LOAD
Kitchen counter 1	20A AFCI/GFCI	12/2 NM-B	Small appliances
Kitchen counter 2	20A AFCI/GFCI	12/2 NM-B	Small appliances
Dishwasher	20A	12/2 NM-B	1.5 kW
Microwave	20A	12/2 NM-B	1.2 kW
Lighting	15A AFCI	14/2 NM-B	10 x 12 W LED

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
200A main panel & breakers (supply + fit)	1	unit	$1,650.00	$1,650.00
New 20A kitchen circuits	4	circuit	$210.00	$840.00
GFCI / AFCI outlets installed	8	outlet	$75.00	$600.00
LED recessed downlights	10	fixture	$95.00	$950.00
Under-cabinet lighting & switch	1	job	$240.00	$240.00
Wire, conduit & boxes	1	lot	$380.00	$380.00
Permit & inspection fee	1	job	$225.00	$225.00

Subtotal	$4,885.00
Tax (7.25%)	$354.16
TOTAL	**$5,239.16**

TERMS & CONDITIONS

- All work to NEC and local code; permit pulled by contractor.
- Power will be off for approx. 4 hours during the panel change.
- 40% deposit to order the panel; balance after passed inspection.
- Workmanship warranty 2 years; fixtures per manufacturer.

Accepted by (name & signature)

Date