Electrical Work Estimate

BrightSpark Electrical Contractors · 123 Business Road · Your City, ST 00000 · (555) 010-2030 · hello@yourcompany.com

Quote No. ELC-2026-0148
Date 11/12/2026

Customer name	Natalie Brooks	**Address / site**	33 Elm Row, Charlotte
Job	EV charger + outdoor outlets	**Charger**	48A Level 2, hardwired
Run length	35 ft from panel	**Date**	November 26, 2026
Phone		**Email**	

Item	Description	Qty	Unit	Rate	Amount
1	Level 2 EV charger install (hardwired)	1	job	$650.00	$650.00
2	60A breaker & 6 AWG copper run	35	ft	$9.50	$332.50
3	Exterior GFCI weatherproof outlets	2	outlet	$145.00	$290.00
4	Motion-sensor flood lights	2	fixture	$120.00	$240.00
5	Load calculation & panel labelling	1	job	$85.00	$85.00
6	Permit & inspection	1	job	$160.00	$160.00

SAFETY & COMPLIANCE CHECKLIST

Before work
- ☐ Permit issued
- ☐ Power isolated & locked out
- ☐ Existing wiring tested

After work
- ☐ GFCI & polarity tested
- ☐ Panel directory labelled
- ☐ Final inspection passed

Subtotal	$1,757.50
Tax (7.25%)	$127.42
TOTAL	**$1,884.92**

TERMS & CONDITIONS

1. Charger unit supplied by client.
2. Panel upgrade quoted separately if load calc fails.
3. Payment due on completion.
4. 2-year workmanship warranty.

Customer signature	Contractor signature	Date