Fence Estimate

Runs, posts, pickets & gates

YOUR LOGO

TrueLine Fence Company

123 Business Road · Your City, ST 00000 · (555) 010-2030 · hello@yourcompany.com

Style: 6 ft cedar privacy, dog-ear

Posts: 4x4 pressure-treated, 8 ft o.c.

Gates: 1 walk gate, 1 double drive gate

Customer Jessica Alvarez

Site 1408 Prairie Lane, Wichita

Quote No. FEN-2026-0208

Date 11/18/2026

STEP 1 · FENCE RUNS

Fence run	Length (ft)	Post spacing (ft)	Sections
Back line	96.0	8.0	**12**
Left side	120.0	8.0	**15**
Right side	120.0	8.0	**15**
Front return (left)	18.0	8.0	**3**
Front return (right)	18.0	8.0	**3**
		Total sections	**48**

STEP 2 · SETTINGS

Total fence length (ft) from the runs	**372**
Corners / run ends sharing a post	4
Line posts needed	**49**
Pickets (5.5" wide, 2 per ft)	**812**
2x4 rails (3 per section)	**144**

STEP 3 · PRICE (quantities come from the take-off)

Item	Qty	Unit	Rate	Amount
Cedar pickets 5.5" x 6 ft	**812.0**	each	$3.60	**$2,923.20**
4x4x8 PT posts	**49.0**	each	$16.00	**$784.00**
2x4x8 PT rails	**144.0**	each	$9.00	**$1,296.00**
Concrete for posts (2 bags each)	**98.0**	bag	$6.50	**$637.00**
Installation labour	**372.0**	lin ft	$14.00	**$5,208.00**
Walk gate 4 ft with hardware	1.0	each	$385.00	**$385.00**
Double drive gate 12 ft	1.0	each	$950.00	**$950.00**

Terms

- Customer to confirm property lines; we call 811 to locate utilities before digging.
- Posts set 2 ft deep (3 ft for 8 ft fences) in concrete.
- Rock or roots needing a jackhammer: $45 extra per post.
- HOA approval is the homeowner's responsibility.

Subtotal	$12,183.20
Tax %	7.50
Tax	$913.74
TOTAL	**$13,096.94**
Deposit %	40
Deposit due	$5,238.78

Accepted by: _____ Date: _____

Cream cells = measurements, yellow = settings. Add rows inside each table; all quantities and totals recalculate.