Roofing Options Quote

Compare three shingle packages side by side



Summit Roofing & Exteriors
123 Business Road · Your City, ST 00000
(555) 010-2030 · hello@yourcompany.com
Roof type: Gable, 6/12 pitch, 1 layer to remove
Roof area: 2,100 sq ft (21 squares + 10% waste)
Material: Architectural asphalt shingles, charcoal

Prepared for	James Walker
Site	309 Pine Hill Road, Columbus
Quote No.	RF-2026-0169
Date	11/12/2026

Line item	Qty	Unit	3-Tab (Good)	Architectural (Better)	Designer (Best)
Rate per unit for each option →					
Tear-off & disposal (1 layer)	21	square	**$1,365.00**	**$1,365.00**	**$1,365.00**
rate			*$65.00*	*$65.00*	*$65.00*
Shingles incl. waste	23	square	**$2,185.00**	**$3,105.00**	**$4,830.00**
rate			*$95.00*	*$135.00*	*$210.00*
Underlayment	23	square	**$345.00**	**$506.00**	**$690.00**
rate			*$15.00*	*$22.00*	*$30.00*
Ice & water shield	4	roll	**$380.00**	**$380.00**	**$560.00**
rate			*$95.00*	*$95.00*	*$140.00*
Flashing, drip edge & vents	1	lot	**$520.00**	**$640.00**	**$890.00**
rate			*$520.00*	*$640.00*	*$890.00*
Installation labour	23	square	**$2,300.00**	**$2,530.00**	**$2,990.00**
rate			*$100.00*	*$110.00*	*$130.00*
		Subtotal	$7,095.00	$8,526.00	$11,325.00
		Tax %	0.00	0.00	0.00
		Tax	$0.00	$0.00	$0.00
		TOTAL	**$7,095.00**	**$8,526.00**	**$11,325.00**

WHAT EACH OPTION INCLUDES

3-Tab (Good): 25-yr 3-tab shingles, felt underlayment, 2-yr workmanship

Architectural (Better): 30-yr architectural shingles, synthetic underlayment, ridge vent, 10-yr workmanship

Designer (Best): 50-yr designer shingles, full ice & water barrier, copper valleys, 25-yr workmanship

Selected option (tick): ☐ 3-Tab (Good) ☐ Architectural (Better) ☐ Designer (Best)

Terms

- Rotten decking replaced at $75 per sheet if found (not included).
- Manufacturer 30-year shingle warranty + 10-year workmanship warranty.
- 1/3 deposit on signing, 1/3 on material delivery, balance on completion.
- Estimate valid for 30 days; insurance claims assistance available.

Customer signature: _____ Date: _____